SASKTEL COLOCATION - SASKATOON NORTH

FACILITY SPECIFICATIONS

SPACE

FACILITY SIZE

- 9,650 sq ft floor space
- Expandable to 30,000 sq ft

DEPLOYMENT

- Racks, cage
- 45U + 52U rack

CONNECTIVITY

CARRIER AVAILABILITY

- Two distribution rooms (network diversity)
- Two redundant fibre entrances
- Alternate carrier options
- · 1 GB shared bandwidth

CROSS CONNECTS

- Fibre
- Copper

SASKTEL NETWORK OPTIONS

- LANspan
- LANspan IP
- Dedicated Internet
- Dedicated Internet Border Gateway Protocol (BGP)
- Virtual Private LAN Service (VPLS)

MONITORING AND SECURITY

24/7 MONITORING

- Onsite experienced staff maintain the data centre infrastructure
- Alarming and support for the data centre environment

ACCESS

- · Key cards
- Biometric access
- · Mantrap entry
- Security kiosk at entrance
- Controlled building and data centre access

CAMERAS

• Motion detection Internet Protocol (IP) cameras

SECURITY OFFICERS

24/7/365 staffed

STRUCTURE

FLOOR LOADING

Slab floor

CEILING HEIGHT

• 10' clear height

RELIABILITY

GENERATORS

• N+1 redundancy (2 Generators 2.5 MW each)

UPTIME

- 99.999% uptime SLA
- · 100% historical portfolio uptime

FUEL STORAGE

• Up to 3 days

UPS

• N+1 paralleled and synchronized (2x 1.35 MW UPS)

COOLING

- N+1 redundancy
- 340 tonnes capacity

FIRE SUPPRESSION

- Double interlock pre-action fire suppression system
- Very Intelligent Early Warning (VIEW) laser cross-zoned smoke detectors

COMPLIANCE AND CERTIFICATIONS

ENVIRONMENT GUIDELINES

• ASHRAE Environmental Guidelines followed

UPTIME INSTITUTE CERTIFICATION

AUDIT

• SOC2 Type 2 Report

AMENITIES

2 STAGING ROOMS

- Booked on availability
- 10 Mbps high speed connection

WORKSPACE

• 2 hotel spaces and boardrooms for team meetings or training

LOADING DOCK

· Loading dock lift

LOCKERS

• Customer delivery lockers for equipment delivery

SUPPORT

OPERATIONS

• 24/7/365 remote hands

TECHNICAL

- Tier 1 SaskTel Business First Support Team (BFST)
- Tier 2 and 3 SaskTel data centre team

PROFESSIONAL SERVICES

- Migration planning
- · Equipment installation

